

RICHMOND METROPOLITAN TRANSPORTATION AUTHORITY

---

RICHMOND EXPRESSWAY SYSTEM

CONTRACT NO. MR-2024

MISCELLANEOUS REPAIRS

---

ADDENDUM NO. 2

May 29, 2024

**Response to Questions**

Pursuant to the Invitation to Bid Document and Pre-Bid Meeting held on May 14, 2024, all project related inquiries were due by 1:00 P.M on May 23, 2024.

With no further inquiries forthcoming, the Authority offers the following questions received and their responses:

**Question 1**

ITEM #39 BOULEVARD BRIDGE DOWNSPOUT RE-ALIGNMENT requires repairs of both trusses of the Boulevard Bridge. The Boulevard Bridge has a weight limit of 7,500 lbs per signage prior to the bridge. Please advise if this weight limit can be temporarily adjusted in order to accommodate a hydra platform and or snooper truck which will allow access from the top of the bridge deck to the downspouts.

**Response** - Temporary adjustment to the weight limit will be made pending review by the Engineer of submittal for particular equipment to be used. On recent tasks, a trailer mounted hydra platform has been utilized to access below the deck.

**Question 2**

For items that require jacking and blocking of beams; if steel jacking stiffeners are needed, can these be left in place?

**Response** - Yes, any stiffeners shown in the approved jacking and blocking plans may be left in place, provided they are primed and painted to match existing steel.

ADDENDUM NO. 2

5/29/2024